		STANDARD OPERATING PROCEDURE		
		SOP No.:	SOP-ED-018-01	Effective Date:
	Discovery Labs	Supersedes:	SOP-ED-018-00	Next Review Date:
	,	Department:	Engineering	Page:

SOP No.:	SOP-ED-018-01	Effective Date:	17.08.2017	
Supersedes:	SOP-ED-018-00	Next Review Date:	16.08.2020	
Department:	Engineering	Page:	1 of 2	

TITLE: OPERATING PROCEDURE FOR CHILLING PLANT

PURPOSE: 1.0

To describe a procedure for operation of Chilling plant.

2.0 **SCOPE:**

This procedure is applicable to operation of Chilling plant at Discovery Laboratories Pvt. Ltd.

3.0 **RESPONSIBILITY:**

3.1 Electrician

Is the responsible to operate Chilling plant

3.2 **Engineer:**

Is responsible to monitor the activity

4.0 **DEFINITIONS: NIL**

5.0 **PROCEDURE:**

- Ensure that the RT water circulation is available to condenser 5.1
- 5.2 Ensure that the Brine solution level in brine storage tank
- 5.3 Check the specific gravity of Brine solution.
- 5.4 Open the inlet and outlet valves of condenser and chiller respectively.
- 5.5 Ensure that the Freon gas in the compressor by checking the suction pressure
- 5.6 Check the oil level in the compressor if require make up oil
- 5.7 Switch on the condenser pump, chiller pump and check the pressure across the condenser and chiller. (Pressure should be 1.5 to 2 kg/cm²)
- 5.8 Open the discharge and suction valves of the compressor.
- 5.9 Switch on the compressor main switch.
- 5.10 Check the suction, discharge and oil pressure of the compressor.

	Prepared by	Reviewed by	Approved by
Sign & Date			
Name	Ch. Shankar	M. Ramesh	Ch. Mahendar Reddy
Department	Engineering	Engineering	Quality Assurance

•*•	STANDARD OPERATING PROCEDURE				
ם ל	SOP No.:	SOP-ED-018-01	Effective Date:	17.08.2017	
Discovery Labs	Supersedes:	SOP-ED-018-00	Next Review Date:	16.08.2020	
,	Department:	Engineering	Page:	2 of 2	
TITLE: OPERATING PROCEDURE FOR CHILLING PLANT					

5.11 Whenever the brine reaches required temperature start the secondary pump and give it to the process.

6.0 FORMATS / ANNEXURE(S): NIL

7.0 CHANGE HISTORY:

Revision No.	Effective Date	Details of Revision	Ref. CCF No.	Remarks
00	01.01.2017	New SOP	ED-CRF-	
			006/16	
01	17.08.2017	1. SOP format changed in line with SOP-QA-	CCF/GEN/	
		001-05.	17007	

	Prepared by	Reviewed by	Approved by	
Sign & Date				
Name	Ch. Shankar	M. Ramesh	Ch. Mahendar Reddy	
Department	Engineering	Engineering	Quality Assurance	